



Timothy Hayden, Director  
Roberta L. Baker, Procurement Officer

**CALVERT COUNTY  
DEPARTMENT OF FINANCE & BUDGET  
PROCUREMENT OFFICE**

150 Main Street, Suite 107  
Prince Frederick, Maryland 20678  
410-535-1600 • 301-855-1243  
www.calvertcountymd.gov

*Board of Commissioners*  
Earl F. Hance  
Mike Hart  
Thomas E. Hutchins  
Kelly D. McConkey  
Steven R. Weems

May 9, 2019

**ADDENDUM NO. 4**

Board of County Commissioners

ITB 2019-095  
Demolition and Construction  
Prince Frederick Volunteer Fire Department (Company 2)  
Prince Frederick, Calvert County, Maryland

To Prospective Bidders:

Following is an addendum to the referenced specifications. Please acknowledge receipt of this addendum by executing the signature block provided below. This signed addendum should be included with your proposal. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the specifications and supplements and modifies them as indicated below:

**Page 1.3, DOCUMENTS REQUIRED UPON SUBMISSION, 10., Revision**

10. Major Subcontractors with foreman's information and foreman's previous three (3) projects. Foreman's previous (3) project information, if not available at time of bid submittal, may be submitted prior to award.

**Page 2.2, Revise and Replace**

Revise and replace page 2.2 with revision dated May 9, 2019 attached to this Addendum No. 4.

**Page 4.9, E., 1<sup>st</sup> Sentence, Revision**

- E. Major Subcontractors with foreman's information and foreman's previous three (3) projects. Foreman's previous (3) project information, if not available at time of bid submittal, may be submitted prior to award.

**Page 01 23 00-2, 1.05, H., Deletion**

Delete H. Deduct No. 8: Apparatus Bay Floor Heating System in its entirety.

**Page 01 23 00-2, 1.05, I. Revise**

From: I. Deduct No. 9: Stair Railing in Stair #1 and Stair #2  
TO  
To: H. Deduct No. 8: Stair Railing in Stair #1 and Stair #2

CONTRACTOR'S LEGAL BUSINESS NAME: \_\_\_\_\_

AUTHORIZED SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_

Mailing Address: 175 Main Street, Prince Frederick, Maryland 20678  
Maryland Relay for Impaired Hearing or Speech: 1-800-735-2258

**Page 08 36 00-1, 1., Revision**

- B. Electric Operators and Controls, including Trolley Operators

**Page 08 36 00-2, 2.1, B., Revise**

- B. Substitutions. Substitutions of an equal product that meets or exceeds all performance requirements of the construction documents shall be considered. Substitution request shall be submitted for consideration.

**Page 08 36 00-3, 2.04, D. Addition**

Provide standard follow-the-roof pitch in Apparatus Bays. Wash Bay 132 shall receive standard 90-degree track. No high lift shall be provided at any location.

**Page 11 31 00-2, 2.1 MANUFACTURERS, A., Revision**

- A. The design for each residential appliance is based on the product named. Substitute products shall be considered for any products named within this Section provided the products meet or exceed the product named and is in compliance with all requirements.

**Drawing A6.02, Revision**

Windows shall be single hung with bottom sash sliding up.

**Drawing W2, W3, and W4, Revision**

Windows shall be single hung with bottom sash sliding up.

**Sheet S1.01 Foundation Plan; Note 1.C., Revision**

C 8" thick concrete slab on grade, place SOG over 10 mil vapor retarder and 4" stone base.

CONTRACTOR'S LEGAL BUSINESS NAME: \_\_\_\_\_

AUTHORIZED SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_

**REVISED MAY 9, 2019 – ADDENDUM NO. 4**

<b>DEDUCT ALTERNATES (IF REQUIRED AND APPROVED BY CALVERT COUNTY GOVERNMENT)</b>			
<b>ITEM #</b>	<b>DESCRIPTION</b>	<b>UNIT OF MEASURE</b>	<b>TOTAL</b>
1	Provide knockout floor panels for future firepoles (2) not provided under this alternate. Delete Doors and Frames P12 and P22. Flooring and Wall Finishes to match Adjoining Rooms.	Lump Sum	\$
2	Use Hardware set 32.1 in lieu of Hardware Set 32	Lump Sum	\$
3	Room 102 shall be concrete broom finish	Lump Sum	\$
4	Delete All Wall Covering - WP-1, WP-2, WP-3, and Finish Walls with Paint P-3	Lump Sum	\$
5	Delete all FRP Panelling, except at Mop Sink Surrounds. Finish is paint P-3.	Lump Sum	\$
6	Delete Lighting Control System. Use Standard On/Off Switch with dimmer ability	Lump Sum	\$
7	Appliances. Deduct: On Sheet A4.04, Delete Items B, C, D, E, F, G, H, I, J (Keep Hood), K, N, and Q. Provide all roughins, outlets and hookups as indicated on the documents.	Lump Sum	\$
8	Stair #1 and #2 – change to a 3 rail railing similar to washbay railing	Lump Sum	\$

***Verify math calculation. In the event of errors in computation, unit price(s) shall be the determining factor for the total(s).***

CONTRACTOR'S LEGAL BUSINESS NAME: \_\_\_\_\_

AUTHORIZED SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_