



Hatched area may be used as laydown area and/or contractor parking. No ground is to be cleared for this purpose. Any disturbed areas must have appropriate erosion and sediment control measures in place, which must also be added to the Erosion and Sediment Control Plan. Used area cannot extend beyond the property limits. Road must be properly maintained throughout the project and cannot be blocked. Road and any used areas must be restored to their original condition upon completion of the project.